

## CEE CERNAVODA

Nr. Crt	Obiectiv	U.M.	Cantitati Totale
<b>1. DRUMURI</b>			
<b>1.1 Drumuri Existente Modernizate (L =2221 m)</b>			
1	Sapatura	mc	3,110.00
2	Umplutura	mc	900.00
3	Strat de forma cu stabilizare 40 cm cu liant hidraulic 3%	mc	7,120.00
4	Piatra Sparta 0 - 63 - 15 cm	mc	2,780.00
5	Piatra Sparta 0 - 32 - 10 cm	mc	2,135.00
<b>1.2 Drumuri Noi (L = 1525 m)</b>			
1	Sapatura	mc	1,550.00
2	Umplutura	mc	3,080.00
3	Strat de forma cu stabilizare 40 cm cu liant hidraulic 3%	mc	3,800.00
4	Piatra Sparta 0 - 63 - 15 cm	mc	1,525.00
5	Piatra Sparta 0 - 32 - 10 cm	mc	1,220.00
<b>1.3 Drum Temporar Nou (L = 571 m)</b>			
1	Sapatura	mc	1,040.00
2	Umplutura	mc	60.00
3	Strat de forma cu stabilizare 40 cm cu liant hidraulic 3%	mc	1,291.00
4	Piatra Sparta 0 - 63 - 15 cm	mc	480.00
5	Piatra Sparta 0 - 32 - 10 cm	mc	360.00
<b>2. PLATFORME</b>			
<b>2.1 Platforme Permanente ( 3 buc = 2965 mp)</b>			
1	Sapatura	mc	4,300.00
2	Umplutura	mc	2,410.00
3	Strat de forma cu stabilizare 40 cm cu liant hidraulic 3%	mc	960.00
4	Geotextil	mp	3,300.00
5	Piatra Sparta 0 - 63 - 20 cm	mc	672.00
6	Geogrila triaxiala	mp	3,300.00
5	Piatra Sparta 0 - 32 - 20 cm	mc	672.00
<b>2.2 Platforme Temporare (3 buc = 9632 mp)</b>			
1	Sapatura	mc	9,584.00
2	Umplutura	mc	5,400.00
3	Strat de forma cu stabilizare 40 cm cu liant hidraulic 3%	mc	3,880.00
4	Piatra Sparta 0 - 63 - 15 cm	mc	2,115.00
5	Piatra Sparta 0 - 32 - 15 cm	mc	2,115.00
<b>3. SUPRALARGIRI - TEMPORARE</b>			
1	Sapatura	mc	4,480.00
2	Umplutura	mc	770.00
3	Strat de forma cu stabilizare 40 cm cu liant hidraulic 3%	mc	2,330.00
4	Piatra Sparta 0 - 63 - 15 cm	mc	1,000.00
5	Piatra Sparta 0 - 32 - 10 cm	mc	200.00